

*"A place where learning has no limits and together we work for the success of all."*

The Harrisonburg City Schools School Nutrition Program is seeking price quotes for fabrication work to convert a Blue Bird bus that is currently a "bookmobile" into a mobile meals bus. Please see the specifications for this work listed below.

- Demo: Remove book shelves and bases along sides of bus. Remove heater from base at rear of bus and reinstall into base of new seating. Remove wooden wall, bench seat, and desk at rear of bus. Dispose of all debris.
- Rear Entry: Remove and replace rear panel to allow for new equipment to be brought through rear entrance. Replacement panels must be removable to allow for future equipment removal and replacement.
- Wall Panels: Must be 20 gauge stainless steel type 304 with a #3 brush finish, approximately 48" linear feet x 78" tall. Brace and fur out walls as needed. Trim with stainless steel divider strips and cap strips.
- Work Counter: Create enclosed base with bottom and center shelf, hinge doors with paddle latches, 18 gauge stainless steel base, 14 gauge stainless steel top with 4" rear backsplash, 30" deep x 36" tall, mounted on 6" stainless steel legs. Build in 2 each refrigerator built-in (FX-1UC or equal to be purchased separately and delivered to fabricator)
- Seating with Storage Below: Bench seat, mounted on cabinet base (15'x16" tall x 25" deep) 16 gauge stainless steel back support mounted to wall, 16 gauge stainless steel bench seat with removable vinyl cushions (removable for cleaning) attached with Velcro, cabinet base 18 gauge stainless steel with hinge doors and paddle latches.
- Front Cabinet: Remove existing under counter refrigerator and replace with an 18 gauge stainless steel insert, bottom and center shelf, hinge door with paddle latch.
- Hand Washing Sink: Self-contained unit, 16 gauge stainless steel top with 4" splash on rear, marine edge on three sides, 18 gauge stainless steel enclosed base with hinge door, 12 gallon fresh water and 16 gallon gray water tanks, water heater, 120-V water pump with pressure switch, 1 each 12"x14"x5" deep drop-in sink with goose neck faucet.
- Labor and material to set, secure, and hook up all equipment (purchased separately and shipped to fabricator) to meet state and local codes. All electrical wiring should be included in this quote. Equipment to be set, secured, and hooked up includes two built in refrigerated drawers (referenced above in Work Counter bullet), milk cooler, and heated cabinet.
- All custom fabrication must be performed by an approved NSF manufacturer.
- **A mandatory site visit is required prior to bid date to review scope of work.**

Price quotes are due by email to Andrea Early, Executive Director of School Nutrition, [aeary@harrisonburg.k12.va.us](mailto:aeary@harrisonburg.k12.va.us) no later than 4:00 April 28, 2017.

For more information or to set up a site visit, please contact Ms. Early at the email above or by phone at 540-437-3300.